

Innovative Research on the Practice of Large-span-Span

Formatted: Font: Not Italic

Prestressed Concrete Beam Construction Technology in Housing Construction

Abstract: Large-span prestressed concrete beam is a structural form widely used in modern buildings, and the rationality of its construction technology is directly related to the engineering quality and safety. Article on the analysis of large span prestressed concrete beam construction points, on the basis of new template support system application, steel connection, high performance concrete mix ratio design, intelligent tension system application of key construction technology, and discusses the BIM technology application, prefabricated construction, green construction process optimization and innovation. The results show that the construction technology of large-span prestressed concrete beam is feasible and effective, which can provide a reference for similar projects.

Commented [DS1]: Highlight the key benefits, such as increased efficiency or safety improvements, to provide a stronger initial impression

Introduction

Large-span prestressed concrete beam can effectively increase the space span of the building, expand the use function of the building, and improve the quality of the space, so it is widely used in modern buildings. However, the construction is difficult, and there are high technical requirements for formwork support systems, reinforcement engineering, concrete engineering, prestressed tension technology, etc. [6,7]. It is necessary to deeply study the key construction technology, optimize the construction technology, and innovate the construction method, so as to ensure the quality of the project and improve the construction efficiency.

Commented [DS2]: Refer to worldwide sustainable construction trends to demonstrate the study's significance.

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Strikethrough

2. Construction points of long-span prestressed concrete beam

2.1 Formwork works and support system

Formwork is the key of concrete construction, which is particularly important for long-span prestressed concrete beams. First of all, the section size and the linear shape of the beam body should be strictly controlled to ensure that the flatness of the bottom mold meets the standard requirements, the height difference of the bottom mold should be controlled within $\pm 2\text{mm}$, and the height difference of the two adjacent templates should not exceed 1mm. Second, the bracket system needs to be accurately calculated and specially designed, and reviewed by a third party. The step distance of the support pole should be 1.0m, the horizontal pole step distance

Commented [DS3]: Include a brief comparison of traditional and advanced formwork systems

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Strikethrough

should be 1.5m, and the layout distance of the vertical and horizontal scissors support should be 2.0m. The support foundation should be ~~set established~~ on a solid foundation, with ~~the~~ sleepers to ensure that the support does not sink [8,9]. At the same time, the support shall be set with ~~an~~ adjustable mechanism to facilitate tuning during construction. During the construction process, dynamic monitoring should be strengthened and ~~adjusted in a timely manner~~ ~~timely adjusted~~ to prevent beam deformation. When the beam span is greater than 24m, the deformation of the support system should be specially ~~calculated~~ ~~calculated~~ [1].

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Not Superscript/ Subscript

Formatted: Not Superscript/ Subscript

Commented [DS4]: Include a brief discussion of obstacles and mitigation strategies for adopting these measures.

2.2 Rebar engineering

Prestressed steel beam and non-prestressed steel reinforcement are generally used for long-span prestressed concrete beams. Prestressed steel bundle should be low loose high strength steel strand, ~~non-prestressed steel~~ can be hot rolled or cold rolled ribbed steel. The stirrup should be ϕ 8mm@50mm, the non-anchorage area ~~shall should~~ be ϕ 8mm@100mm, and the limb length should be 80mm. The diameter of the upper and lower longitudinal reinforcement of the beam web shall be 12mm, and the spacing shall be 200mm [10]. When the beam height exceeds 1.2m, the vertical reinforcement of the web can be arranged by ϕ 10mm@200mm. The minimum diameter of ~~the~~ longitudinal stressed reinforcement is 16mm and the spacing is 200~300mm. The lower longitudinal reinforcement should be arranged along the full length of the beam, and the upper longitudinal reinforcement can use additional tendons according to the force needs. Rebar connection should be preferred by mechanical connection or welding form, and ~~the~~ lap joints should be staggered. The steel frame ~~shall should~~ be lifted in a whole to improve efficiency and ensure quality. The thickness of the protective layer of the steel bar ~~shall must~~ meet the design and specification requirements, and reliable positioning and support measures ~~shall must~~ be taken to avoid ~~the~~ displacement and deformation of the steel bar in the ~~pouring~~ ~~pouring~~ [2].

Formatted: Strikethrough

Formatted: Not Superscript/ Subscript

Commented [DS5]: Add a phrase or two on how the optimized mix design benefits to project sustainability or cost-efficiency

2.3 Concrete works

~~The Large~~ large-span prestressed concrete beam has high requirements ~~on for~~ concrete performance, usually requiring high strength and ~~high performance~~ ~~high performance~~ concrete. The mix ratio of concrete ~~needs to be~~ ~~must be~~ optimized through the test, select raw materials with excellent performance, and strict control of water consumption, slump, gas content, and other indicators. The ~~beam~~ concrete should be poured continuously. If the construction joint needs to be retained, the joint surface should be treated and the grouting pipe should be embedded. ~~The~~ Concrete pouring ~~shall should~~ be carried out in layers. The thickness of each layer ~~shall should~~ be controlled below 500mm [3].

Formatted: Strikethrough

Formatted: Not Superscript/ Subscript

Commented [DS6]: Include a phrase discussing the practical issues and solutions in tensioning large-span beams

2.4 Prestressed tensioning process

Prestressed tension is the key content of ~~large~~ ~~large~~ span concrete beam construction, and tension technology has an important influence on the quality of beam. Prestressed system is

divided into two systems: a cohesive system and an unbonded system. The construction process of cohesive system is relatively complex, but it is more favorable for crack control. When the bonding system is adopted, the high strength steel strand should be selected as ϕ s15.2mm, ϕ s15.7mm or ϕ s21.8mm, and the ultimate strength standard value is not lower than 1860MPa; When the non-bonded system is used, high strength wire such as ϕ 25mm, ϕ 27mm and ϕ 30mm can be used, and the standard value of ultimate strength is not lower than 1570MPa. The tension end anchor should be made of high-quality clip and high strength pad, effectively uniform prestress. The tension should be graded loading, the primary tension should not exceed 25% of the design tension, the secondary tension should not exceed 75% of the designed value, and the interval between the secondary tension and the primary tension should not be less than 1h. During the tension process, the tension and elongation value should be accurately monitored, and then the grouting pressure should be sealed in-on time. The rear tension beam body can be anchored in the end flange plate, but secondary tension is required to compensate for the elastic compression and creep loss of concrete [4].

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Not Superscript/ Subscript

3. Key construction technology

3.1 Application of the new formwork support system

The traditional steel pipe bracket erection method is time-consuming and easily causes concrete surface damage; the new aluminum alloy formwork support system can realize fast loading and unloading and significantly improve the construction efficiency. The new formwork support system is assembled from light aluminum alloy profiles, which can be bolted to quickly build various formwork support frames. It has strong bearing capacity, good stiffness, convenient loading and unloading, can be used, and is more economical and environmentally friendly. The key nodes adopt factory customized standard components, and the site assembly is simple and fast, which can effectively ensure the construction quality. The system has been applied in many major projects in China, and has achieved good results.

Commented [DS7]: Clarify how the implementation of this technology effects overall project deadlines and costs

Formatted: Strikethrough

Formatted: Strikethrough

Commented [DS8]: Recommend adding a comparison of the effectiveness and dependability of conventional approaches.

Formatted: Strikethrough

Formatted: Strikethrough

3.2 Rebar connection

Reinforcement engineering is an important part of concrete construction, and the reinforcement connection method has a great influence on the construction efficiency and cost. The traditional steel bar binding lap method is very time-consuming and laborious. The new sleeve extrusion connection technology can realize the fast and reliable connection of steel bars. This method uses the connection sleeve, through the special hydraulic machinery, the steel bar is inserted into the two ends of the sleeve, extrusion deformation, forming a permanent connection, its strength can reach the tensile limit strength of the steel bar. The technology is simple and fast, and one person and one machine can operate efficiently. The time of connecting a single joint is not more than 2min, which significantly reduces the on-site workload and improves the labor

Formatted: Strikethrough

production efficiency. The sleeve connection does not need to be welded, which can avoid the thermal influence of steel bars, the connection performance is stable and reliable, and save a lot of steel bars, in line with the concept of green construction [5].

3.3 Mix ratio design of high-performance concrete

Large-span prestressed concrete beam has high requirements for concrete strength, durability and other performance indicators, ordinary concrete is often difficult to meet the requirements, and need to use high performance concrete. The design of high performance concrete mix ratio should be optimized on the basis of ordinary concrete mix ratio, mixed with excellent admixture, water reducing agent, etc., and increase the amount of cement, reduce the water-cement ratio, control the sand grading, improve the workability, in order to obtain better strength and durability. Through the reasonable blending of silicon ash and fly ash, the compaction and impermeability of concrete can be further enhanced. In order to ensure the construction performance, the slow coagulation type admixture can be added to extend the setting time, and take into account the slump. The mix ratio of high performance concrete should be optimized through special tests, the best raw materials and dosage should be selected, and the quality control should be strengthened to ensure the consistency and stability of production and supply.

3.4 Application of intelligent tension-drawing system

The key to the construction of prestressed concrete beam is to accurately control the tension and elongation. Traditional manual operation inevitably causes errors and fluctuations. Using intelligent tension system can realize high precision and fully automatic construction. The intelligent tensioning system is controlled by programmable logic controller (programmable logic controller, PLC), integrating oil pump, pressure sensor, displacement sensor and other equipment, which can collect and feedback tensioning data in real time, and automatically adjust according to the set parameters. The system also has functions such as data recording and report analysis, which can realize the digital management and quality traceability of the whole process of tensioning process. The application of the system can ensure that the tension error is controlled within $\pm 2\%$ of the design value, the elongation error is controlled within $\pm 6\%$ of the theoretical value, the construction quality and accuracy are effectively improved, and the labor efficiency can be significantly improved and the labor cost can be saved.

4. Optimization and innovation of construction technology

4.1 BIM technology application

The main application points of BIM technology are as follows: (1) using parametric design technology, Establish a model including the beam body geometry size, material properties, load condition and other parameters, Automatically generate and optimize multiple sets of design

Formatted: Not Superscript/ Subscript

Commented [DS9]: Take into consideration including information about how the selected mix impacts the beam's performance in different environmental conditions.

Formatted: Strikethrough

Formatted: Strikethrough

Formatted: Strikethrough

Commented [DS10]: Provide further details about the implications of employing such systems for long-term monitoring or maintenance.

Commented [DS11]: Recommend including a brief description of limitations of BIM adoption in less technologically advanced regions.

solutions, To improve the design efficiency and quality; (2) ~~Adopt~~ adopt intelligent reinforcement technology, ~~According~~ according to the design scheme and the specification requirements, ~~Automatically~~ automatically generate the reinforcement configuration scheme in the BIM, ~~And~~ and output the feeding list and processing details, Guide the reinforcement construction; (3) ~~Application~~ application of stent intelligent computing technology, ~~According~~ according to the beam body information and the construction specifications, intelligently arrange the supports in the BIM and optimize the specifications and spacing of components, ~~Ensure~~ ensure that the bracket system is safe, reliable, economical and efficient; (4) ~~Using~~ using the virtual construction simulation technology, ~~Three~~ three-dimensional dynamic simulations of the key construction processes on the BIM platform, ~~Optimize~~ optimize the construction process and process, ~~Reasonable~~ reasonable arrangement of resource input, ~~Guide~~ guide the site construction, Improve the level of construction management. The application of BIM technology can significantly improve the construction efficiency of ~~the~~ prestressed concrete beam, ensure the construction quality and safety, and promote the development of construction engineering ~~to in~~ the digital and intelligent direction.

Formatted: Strikethrough

4.2 Prefabricated construction

Pre-fabricated construction is an advanced construction method, in line with the trend of industrialization and information development. The prefabricated construction transfers the traditional site operation to the factory to realize the factory for the factory production of construction parts and parts, which can optimize the allocation of resources, reduce material loss, and improve labor production efficiency. For long-span prestressed concrete beams, the paper innovatively proposes the whole pre-fabricated intelligent construction method of large-span prestressed concrete beams ~~on the basis of analyzing based on the analysis of~~ the advancement of prefabricated buildings. Through the modular design of the beam body, the beam body is divided into several sections, pre-fabricated in the factory to make full use of the mechanized production line to realize standardized and fine manufacturing, so as to significantly improve the concrete performance and surface quality of the beam body. The segment components are transported to the site by transport vehicles, and the construction technology of "overall lifting + sliding in place" is adopted to realize the rapid assembly with the column, wall, and other components, and the overall assembly is realized through the sleeve grouting connection. In the assembly process, the component bolt connection, the prestressed reinforcement, and the continuous longitudinal reinforcement field connection all adopt the robot welding method, which realizes the mechanization and automation of the whole construction process; and improves the construction efficiency and quality. This construction method significantly reduces wet operations on site, improves the utilization rate of turnover materials, reduces personnel demand, and is more

Commented [DS12]: Recommendation for addition: Compare the carbon footprints of conventional and prefabricated building techniques.

Formatted: Strikethrough

Formatted: Strikethrough

economical.

4.3 Green construction

Green construction is ~~the~~^{an} inevitable requirement of the sustainable development of the construction industry. The construction of large-span prestressed concrete beam should fully implement the concept of green construction, pay attention to energy saving, material saving, water saving and land saving, and control the adverse impact of the construction process on the environment. In the construction organization and planning, resource conservation and environmental protection factors should be systematically considered, the construction scheme should be optimized, energy-saving and environmental protection materials should be selected, and clean production mode should be implemented to reduce noise and dust. For materials such as steel bars and formwork, factory processing methods should be adopted as far as possible to reduce on-site cutting and welding operations. Waste wood and steel should be collected by classification and submitted for recycling by professional institutions. For concrete curing, the waste water and reclaimed water should be used first, and the construction wastewater should be reused or discharged according to the standard after treatment. For large mechanical equipment, ^{an} energy-saving type number should be selected, ~~and~~ LED lamps should be used for engineering lighting. Actively apply solar energy, ground source heat pump and other renewable energy, promote prefabricated construction, reduce the site wet operation. Strengthen the education and training of construction personnel, enhance the awareness of green construction, and implement environmental responsibility to each post.

5. Conclusions

Large-span prestressed concrete beam is the key structural form in modern buildings. The systematic study of its construction technology is of great significance to ensure the project quality, improve the construction efficiency and promote the transformation and upgrading of the construction industry. On the basis of analyzing the key construction points, this paper focuses on the key construction technology, ~~and puts forward the construction technology optimization and innovation path~~ ^{of construction technology}. The adoption of advanced concepts and methods such as BIM technology application, prefabricated construction and green construction represents the future development direction of construction engineering. We should further strengthen the linkage of "industry, university, research and application", strengthen the transformation of scientific and technological achievements, improve the technical standards and specifications, and effectively promote the high-quality development of long-span prestressed concrete beam.

References

Commented [DS13]: Add examples

Formatted: Strikethrough

Commented [DS14]: • Make sure the formatting (such as units and technical words) is the same across the manuscript.
• Where appropriate, use flowcharts, tables, or diagrams to improve readability and comprehension.
• To fix small grammatical mistakes and enhance sentence clarity, do a final proofread.

Formatted: Strikethrough

Formatted: Strikethrough

- [1] Zheng Ye, Wei Deqiang. Construction method of large-span cast-in-situ prestressed concrete beam [J]. *Engineering construction*, 2020,52 (8): 53-58.
- [2] Fu Haihua, Hu Min. Research on the application of construction control technology of long-span prestressed concrete continuous girder bridge [J]. *Construction Machinery*, 2023 (8): 101-103,107.
- [3] Zhang Yong, Lu Bing, Shao Yingzi, and so on. Construction technology and quality control of long-span prestressed concrete beam [J]. *Residential Facilities in China*, 2022 (12): 93-95.
- [4] Yue esheng, Xu Haiwen, Liu Zijian. Research on the construction technology of slow bonding and unbonded prestress of long-span concrete beam [J]. *Building mechanization*, 2022,43 (11): 63-67.
- [5] Tan Weikuan. Construction technology of post-tension prestressed concrete beam with large section and large span [J]. *Stone*, 2024 (7): 45-47.
6. Szydłowski R, Labuzek B. Post-tensioned concrete long-span slabs in projects of modern building construction. In *IOP Conference Series: Materials Science and Engineering 2017 Oct 1 (Vol. 245, No. 2, p. 022065)*. IOP Publishing.
7. Yuan JL. The Construction Technique of the Beam Slab Structure being Filled Large-Span Prestressed Lightweight Materials. *Advanced Materials Research*. 2013 Sep 27;743:73-7.
8. Zhao G, Duan S, Sun B, Yuan X. Application on large-span reconstructed structure with external prestressing technology. In *Journal of Physics: Conference Series 2021 Apr 1 (Vol. 1885, No. 4, p. 042042)*. IOP Publishing.
9. Gao QF, Ma QL, Zhang K, Liu CG. Discussion on the excessive deflection in mid-spans of large-span prestressed concrete continuous beam bridges. In *Bridge Maintenance, Safety, Management, Life-Cycle Sustainability and Innovations 2021 Apr 19 (pp. 3618-3624)*. CRC Press.
10. Gao QF, Ma QL, Zhang K, Liu CG. Discussion on the excessive deflection in mid-spans of large-span prestressed concrete continuous beam bridges. In *Bridge Maintenance, Safety, Management, Life-Cycle Sustainability and Innovations 2021 Apr 19 (pp. 3618-3624)*. CRC Press.